

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

		Date	11/27/2023
Item Description	Qty Required	UOM	
Doors	2	Pcs	
Height	Width	Thickness	
2285	2155	36	

1ST FLOOR

Room 105
Room 109
Cladding Right side

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	4	Ash Wood
2	SF000-1	Frame	Top+Bottom	2155	36	22	4	Ash Wood
3	SF000-1	Panel	Panel 1	2209	360	18	2	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	2209	150	18	2	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	2209	650	18	2	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	2209	383	18	2	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	2209	383	18	2	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	2209	150	18	2	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	10	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	4	Ash Wood
11	SF000-4	Panel	Wood for grove	2111	13	5	4	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	4	Ash Wood
13	SF000-6	Frame	Top+Bottom	2111	20	14	4	Ash Wood

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

		Date	11/27/2023
Item Description	Qty Required	UOM	
Doors	3	Pcs	
Height	Width	Thickness	
2285	2125	36	

1ST FLOOR

Room 101 / 120
Room 119
Cladding Right side

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	4 6	Ash Wood
2	SF000-1	Frame	Top+Bottom	2125	36	22	4 6	Ash Wood
3	SF000-1	Panel	Panel 1	<u>2209</u>	<u>330</u>	18	2 3	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	<u>2209</u>	<u>150</u>	18	2 3	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	<u>2209</u>	<u>650</u>	18	2 3	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	<u>2209</u>	<u>383</u>	18	2 3	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	<u>2209</u>	<u>383</u>	18	2 3	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	<u>2209</u>	<u>150</u>	18	2 3	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	10 15	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	4 6	Ash Wood
11	SF000-4	Panel	Wood for grove	2081	13	5	4 6	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	4 6	Ash Wood
13	SF000-6	Frame	Top+Bottom	2081	20	14	4 6	Ash Wood

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

1ST FLOOR

Room 131

Cladding Right side

		Date	11/27/2023
Item Description	Qty Required	UOM	
Doors	1	Pcs	
Height	Width	Thickness	
2285	2165	36	

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	2	Ash Wood
2	SF000-1	Frame	Top+Bottom	2165	36	22	2	Ash Wood
3	SF000-1	Panel	Panel 1	2209	370	18	1	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	2209	150	18	1	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	2209	650	18	1	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	2209	383	18	1	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	2209	383	18	1	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	2209	150	18	1	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	5	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	2	Ash Wood
11	SF000-4	Panel	Wood for grove	2121	13	5	2	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	2	Ash Wood
13	SF000-6	Frame	Top+Bottom	2121	20	14	2	Ash Wood

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

Item Description	Qty Required	UOM	Date
Doors	2	Pcs	11/27/2023
Height	Width	Thickness	
2285	2175	36	

1ST FLOOR

Room 127
Room 116
Cladding Right side

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	4	Ash Wood
2	SF000-1	Frame	Top+Bottom	2175	36	22	4	Ash Wood
3	SF000-1	Panel	Panel 1	2209	380	18	2	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	2209	150	18	2	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	2209	650	18	2	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	2209	383	18	2	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	2209	383	18	2	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	2209	150	18	2	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	10	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	4	Ash Wood
11	SF000-4	Panel	Wood for grove	2131	13	5	4	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	4	Ash Wood
13	SF000-6	Frame	Top+Bottom	2131	20	14	4	Ash Wood

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

1ST FLOOR

Room 132

Cladding Right side

Item Description	Qty Required	UOM	Date
Doors	1	Pcs	11/27/2023
Height	Width	Thickness	
2285	2105	36	

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	2	Ash Wood
2	SF000-1	Frame	Top+Bottom	2105	36	22	2	Ash Wood
3	SF000-1	Panel	Panel 1	2209	310	18	1	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	2209	150	18	1	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	2209	650	18	1	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	2209	383	18	1	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	2209	383	18	1	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	2209	150	18	1	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	5	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	2	Ash Wood
11	SF000-4	Panel	Wood for grove	2061	13	5	2	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	2	Ash Wood
13	SF000-6	Frame	Top+Bottom	2061	20	14	2	Ash Wood

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

1ST FLOOR

Room 124
Room 112
Cladding Right side

Item Description	Qty Required	UOM
Doors	1	Pcs
Height	Width	Thickness
2285	2135	36

Date: 11/27/2023

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	2	Ash Wood
2	SF000-1	Frame	Top+Bottom	2135	36	22	2	Ash Wood
3	SF000-1	Panel	Panel 1	2209	340	18	1	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	2209	150	18	1	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	2209	650	18	1	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	2209	383	18	1	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	2209	383	18	1	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	2209	150	18	1	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	5	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	2	Ash Wood
11	SF000-4	Panel	Wood for grove	2091	13	5	2	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	2	Ash Wood
13	SF000-6	Frame	Top+Bottom	2091	20	14	2	Ash Wood

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

1ST FLOOR

Room 102

Cladding Right side

Item Description	Qty Required	UOM	Date
Doors	1	Pcs	11/27/2023
Height	Width	Thickness	
2285	2130	36	

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	2	Ash Wood
2	SF000-1	Frame	Top+Bottom	2130	36	22	2	Ash Wood
3	SF000-1	Panel	Panel 1	2209	335	18	1	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	2209	150	18	1	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	2209	650	18	1	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	2209	383	18	1	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	2209	383	18	1	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	2209	150	18	1	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	5	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	2	Ash Wood
11	SF000-4	Panel	Wood for grove	2086	13	5	2	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	2	Ash Wood
13	SF000-6	Frame	Top+Bottom	2086	20	14	2	Ash Wood

Project Name		Hyatt Hotel
Project Code		
Job Order Number		

1ST FLOOR

Room 106

Cladding Right side

Item Description	Qty Required	UOM	Date
Doors	1	Pcs	11/27/2023
Height	Width	Thickness	
2285	2195	36	

All Measurements are in millimetres

	SF#	SF Description	Parts Description	Length	Width	Thickness	Qty	Remarks
1	SF000-1	Frame	Side	2285	36	22	2	Ash Wood
2	SF000-1	Frame	Top+Bottom	2195	36	22	2	Ash Wood
3	SF000-1	Panel	Panel 1	2209	400	18	1	Mdf +Oak Veneer
4	SF000-1	Panel	Panel 2	2209	150	18	1	Mdf +Oak Veneer
5	SF000-1	Panel	Panel 3	2209	650	18	1	Mdf +Oak Veneer
6	SF000-1	Panel	Panel 4	2209	383	18	1	Mdf +Oak Veneer
7	SF000-1	Panel	Panel 5	2209	383	18	1	Mdf +Oak Veneer
8	SF000-1	Panel	Panel 6	2209	150	18	1	Mdf +Oak Veneer
9	SF000-2	Panel	Wood for grove	2209	13	5	5	Ash Wood
10	SF000-3	Panel	Wood for grove	2219	13	5	2	Ash Wood
11	SF000-4	Panel	Wood for grove	2151	13	5	2	Ash Wood
12	SF000-5	Frame	Side	2241	20	14	2	Ash Wood
13	SF000-6	Frame	Top+Bottom	2151	20	14	2	Ash Wood